



Test Report: HRP-450-48

450W Single Output With PFC Function

■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

Control Function Test

Component Stress Test

■ SAFETY & E.M.C. TEST

Safety Test

E.M.C. Test

■ RELIABILITY TEST

ENVIRONMENT TEST

DESIGN VERIFY TEST

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1 : 240 mVp-p (Max)	I/P : 230VAC O/P : FULL LOAD Ta : 25°C	V1 : 140 mVp-p (Max)	P
2	OUTPUT VOLTAGE ADJUST RANGE	CH1 : 40.8V ~ 55.2 V	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	38.23 V ~ 58.38 V/ 230 VAC 38.23 V ~ 58.38 V/ 115 VAC	P
3	OUTPUT VOLTAGE TOLERANCE	V1 : 1 % ~ -1 % (Max)	I/P : 100 VAC / 264 VAC O/P : FULL/ MIN LOAD Ta : 25°C	V1 : 0.08 % ~ -0.08 %	P
4	LINE REGULATION	V1 : 0.2% ~ -0.2 % (Max)	I/P : 100 VAC ~ 264 VAC O/P : FULL LOAD Ta : 25°C	V1 : 0.02 % ~ -0.02 %	P
5	LOAD REGULATION	V1 : 0.5 % ~ -0.5 % (Max)	I/P : 230 VAC O/P : FULL ~ MIN LOAD Ta : 25°C	V1 : 0.08 % ~ -0.08 %	P
6	SET UP TIME	230VAC : 1000 ms (Max) 115VAC : 2500 ms(Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 172 ms 115VAC/ 344 ms	P
7	RISE TIME	230VAC : 100 ms (Max) 115VAC : 100 ms (Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 13 ms 115VAC/ 13 ms	P
8	HOLD UP TIME	230VAC : 16 ms (TYP) 115VAC : 16 ms (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 24 ms 115VAC/ 19 ms	P
9	OVER/UNDERSHOOT TEST	< ±5%	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	TEST : < 5 %	P
10	DYNAMIC LOAD	V1 : 4800 mVp-p	I/P : 230 VAC (1).O/P : FULL /Min LOAD 90%DUTY/ 1KHZ (2).O/P : FULL /Min LOAD 50%DUTY/ 120HZ Ta : 25°C	(1). 811mVp-p (2). 2468mVp-p	P

INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	100VAC~264 VAC	I/P : TESTING O/P : FULL LOAD Ta : 25°C	70 V~264V	P
			I/P : LOW-LINE-3V= 97 V HIGH-LINE+15%=300 V O/P : FULL/MIN LOAD ON : 30 Sec . OFF : 30 Sec 10MIN (AC POWER ON/OFF NO DAMAGE)	TEST : OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P : 100 VAC ~ 264 VAC O/P : FULL~MIN LOAD Ta : 25°C	TEST : OK	P
3	POWER FACTOR	0.95 / 230 VAC(TYP) 0.99 / 115 VAC(TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	PF= 0.98 / 230 VAC PF= 1 / 115 VAC	P
4	EFFICIENCY	89.5% (TYP)	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	90.06 %	P
5	INPUT CURRENT	230V/ 2.4 A (TYP) 115V/ 5 A (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I= 2.24 A/ 230 VAC I= 4.56 A/ 115 VAC	P
6	INRUSH CURRENT	230V/ 70 A (TYP) 115V/ 35 A (TYP) COLD START	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I= 68 A/ 230 VAC I= 34 A/ 115 VAC	P
7	LEAKAGE CURRENT	< 1.5 mA / 240 VAC	I/P : 264 VAC O/P : Min LOAD Ta : 25°C	L-FG : 1.15 mA N-FG : 0.6 mA	P

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	105% ~ 135 %	I/P : 230 VAC I/P : 115 VAC O/P : TESTING Ta : 25°C	115.1 %/ 230 VAC 118.2 %/ 115 VAC Constant current limiting, recovers automatically after fault condition is removed	P
2	OVER VOLTAGE PROTECTION	CH1 : 57.6V ~ 67.2 V	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	62.82 V/ 230 VAC 62.75 V/ 115 VAC Shut down Re- power ON	P
3	OVER TEMPERATURE PROTECTION	SPEC : Shut down o/p voltage , recovers automatically after temperature goes down	I/P : 230 VAC O/P : FULL LOAD	O.T.P. Active Shut down o/p voltage , recovers automatically after temperature goes down	P
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P : 264 VAC O/P : FULL LOAD Ta : 25°C	NO DAMAGE Constant current limiting, recovers automatically after fault condition is removed	P

CONTROL FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	DC OK SIGNAL	PSU turn on : 3.3 ~ 5.6V ; PSU turn off : 0 ~ 1V	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	PSU turn on : 5.23 V PSU turn off : 0.018 V	P
2	REMOTE SENSE	>0.5V	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	> 0.5 V	P
3	FAN ON/OFF control test	FAN ON : 20%± 10%	I/P : 230 VAC O/P : TESTING Ta : 25°C	> 23.7 %LOAD FAN ON < 18.94 %LOAD FAN OFF	P

COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor (D to S) or (C to E) Peak Voltage	Q3 Rated : IRFP460A 20A/500V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2) Output Short (3)Full load continue Ta : 25°C	(1) 428 V (2) 406 V (3) 378 V	P
2	Diode Peak Voltage	Q 101 Rated : FME-220B 20A/150V Q 103 Rated : SF20LC30 20A/300V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2)Output Short (3)Full load continue Ta : 25°C	(1) 149 V (2) 149 V (3) 148 V (1) 272 V (2) 270 V (3) 257 V	P
3	Input Capacitor Voltage	C5 Rated : 330u/400V 105°C 30*30 HU	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 371.2 V (2) 374.5 V (3) 374.4 V	P
4	Control IC Voltage Test	U1 Rated : FAN4801NY 9.3V~30V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 15.847 V (2) 15.095 V (3) 15.117 V	P
5	Power Transistor (D to S) or (C to E) Peak Voltage	Q 1 Rated : IRFP460A 20A/500V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2) Output Short (3)Full load continue Ta : 25°C	(1) 472 V (2) 390 V (3) 408 V	P

■ SAFETY & E.M.C. TEST

SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P : 3 KVAC/min I/P-FG : 2 KVAC/min O/P-FG : 0.5 KVAC/min	I/P-O/P : 3.6 KVAC/min I/P-FG : 2.4 KVAC/min O/P-FG : 0.6 KVAC/min Ta : 25°C	I/P-O/P : 5.98 mA I/P-FG : 4.75 mA O/P-FG : 3.52 mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P : 500VDC>100MΩ I/P-FG : 500VDC>100MΩ O/P-FG : 500VDC>100MΩ	I/P-O/P : 500 VDC I/P-FG : 500 VDC O/P-FG : 500 VDC Ta : 25°C /70%RH	I/P-O/P : 16.4 GΩ I/P-FG : 15.6 GΩ O/P-FG : 20.7 GΩ NO DAMAGE	P
3	GROUNDING CONTINUITY	FG(PE) TO CHASSIS OR TRACE < 100 mΩ	40 A / 2min Ta : 25°C / 70%RH	8 mΩ	P
4	APPROVAL	TUV : Certificate NO : UL : File NO :			N/A

E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2,-3 CLASS A	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	PASS	P
2	CONDUCTION	EN55022 CLASS B	I/P : 230 VAC (50HZ) O/P : FULL/50% LOAD Ta : 25°C	PASS Test by certified Lab	P
3	RADIATION	EN55022 CLASS B	I/P : 230 VAC (50HZ) O/P : FULL LOAD Ta : 25°C	PASS Test by certified Lab	P
4	E.S.D	EN61000-4-2 INDUSTRY AIR : 8KV / Contact : 4KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
5	E.F.T	EN61000-4-4 INDUSTRY INPUT : 2KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
6	SURGE	IEC61000-4-5 INDUSTRY L-N : 2KV L,N-PE : 4KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
7	Test by certified Lab & Test Report Prepare				

RELIABILITY TEST

ENVIRONMENT TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT																																																																																													
1	TEMPERATURE RISE TEST	MODEL : HRPG-450-24 1. ROOM AMBIENT BURN-IN : 1 HRS I/P : 230VAC O/P : FULL LOAD Ta= 27.1 °C 2. HIGH AMBIENT BURN-IN : 4.5 HRS I/P : 230VAC O/P : FULL LOAD Ta= 50 °C <table><thead><tr><th>NO</th><th>Position</th><th>ROOM AMBIENT Ta= 27.1 °C</th><th>HIGH AMBIENT Ta= 50 °C</th></tr></thead><tbody><tr><td>1</td><td>LF2</td><td>44.4°C</td><td>64.4°C</td></tr><tr><td>2</td><td>U1</td><td>41.7°C</td><td>61.2°C</td></tr><tr><td>3</td><td>L3</td><td>53.0°C</td><td>73.7°C</td></tr><tr><td>4</td><td>C5</td><td>39.8°C</td><td>59.6°C</td></tr><tr><td>5</td><td>D1</td><td>52.1°C</td><td>71.2°C</td></tr><tr><td>6</td><td>Q1</td><td>48.6°C</td><td>68.3°C</td></tr><tr><td>7</td><td>Q4</td><td>41.0°C</td><td>60.9°C</td></tr><tr><td>8</td><td>T1</td><td>50.8°C</td><td>71.0°C</td></tr><tr><td>9</td><td>BD1</td><td>49.9°C</td><td>69.4°C</td></tr><tr><td>10</td><td>TSW1</td><td>45.2°C</td><td>64.7°C</td></tr><tr><td>11</td><td>C18</td><td>41.5°C</td><td>61.2°C</td></tr><tr><td>12</td><td>C61</td><td>42.1°C</td><td>61.4°C</td></tr><tr><td>13</td><td>C105</td><td>34.6°C</td><td>53.4°C</td></tr><tr><td>14</td><td>Q101</td><td>59.5°C</td><td>78.2°C</td></tr><tr><td>15</td><td>Q104</td><td>49.4°C</td><td>68.4°C</td></tr><tr><td>16</td><td>L100</td><td>41.2°C</td><td>61.1°C</td></tr><tr><td>17</td><td>TSW2</td><td>40.9°C</td><td>60.4°C</td></tr><tr><td>18</td><td>C19</td><td>48.6°C</td><td>68.4°C</td></tr><tr><td>19</td><td>D900</td><td>44.1°C</td><td>62.4°C</td></tr><tr><td>20</td><td>U900</td><td>40.5°C</td><td>60.3°C</td></tr><tr><td>21</td><td>T900</td><td>39.3°C</td><td>58.2°C</td></tr><tr><td>22</td><td>C955</td><td>32.7°C</td><td>52.2°C</td></tr></tbody></table>			NO	Position	ROOM AMBIENT Ta= 27.1 °C	HIGH AMBIENT Ta= 50 °C	1	LF2	44.4°C	64.4°C	2	U1	41.7°C	61.2°C	3	L3	53.0°C	73.7°C	4	C5	39.8°C	59.6°C	5	D1	52.1°C	71.2°C	6	Q1	48.6°C	68.3°C	7	Q4	41.0°C	60.9°C	8	T1	50.8°C	71.0°C	9	BD1	49.9°C	69.4°C	10	TSW1	45.2°C	64.7°C	11	C18	41.5°C	61.2°C	12	C61	42.1°C	61.4°C	13	C105	34.6°C	53.4°C	14	Q101	59.5°C	78.2°C	15	Q104	49.4°C	68.4°C	16	L100	41.2°C	61.1°C	17	TSW2	40.9°C	60.4°C	18	C19	48.6°C	68.4°C	19	D900	44.1°C	62.4°C	20	U900	40.5°C	60.3°C	21	T900	39.3°C	58.2°C	22	C955	32.7°C	52.2°C		P
NO	Position	ROOM AMBIENT Ta= 27.1 °C	HIGH AMBIENT Ta= 50 °C																																																																																															
1	LF2	44.4°C	64.4°C																																																																																															
2	U1	41.7°C	61.2°C																																																																																															
3	L3	53.0°C	73.7°C																																																																																															
4	C5	39.8°C	59.6°C																																																																																															
5	D1	52.1°C	71.2°C																																																																																															
6	Q1	48.6°C	68.3°C																																																																																															
7	Q4	41.0°C	60.9°C																																																																																															
8	T1	50.8°C	71.0°C																																																																																															
9	BD1	49.9°C	69.4°C																																																																																															
10	TSW1	45.2°C	64.7°C																																																																																															
11	C18	41.5°C	61.2°C																																																																																															
12	C61	42.1°C	61.4°C																																																																																															
13	C105	34.6°C	53.4°C																																																																																															
14	Q101	59.5°C	78.2°C																																																																																															
15	Q104	49.4°C	68.4°C																																																																																															
16	L100	41.2°C	61.1°C																																																																																															
17	TSW2	40.9°C	60.4°C																																																																																															
18	C19	48.6°C	68.4°C																																																																																															
19	D900	44.1°C	62.4°C																																																																																															
20	U900	40.5°C	60.3°C																																																																																															
21	T900	39.3°C	58.2°C																																																																																															
22	C955	32.7°C	52.2°C																																																																																															
2	OVER LOAD BURN-IN TEST	NO DAMAGE 1 HOUR (MIN)	I/P : 230 VAC O/P : 123 % LOAD Ta : 25°C	TEST : OK	P																																																																																													
3	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P : 264VAC/100VAC O/P : 100 % LOAD Ta= -40 °C	TEST : OK	P																																																																																													
4	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 50 °C NO DAMAGE	I/P : 272 VAC O/P : FULL LOAD Ta= 50 °C HUMIDITY= 95 %R.H	TEST : OK	P																																																																																													
5	TEMPERATURE COEFFICIENT	± 0.03 %(0~50°C)	I/P : 230 VAC O/P : FULL LOAD	± 0.01 %(0~50°C)	P																																																																																													
6	STORAGE TEMPERATURE TEST	1. Thermal shock Temperature : -45°C~ +90°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 5 CYCLE 5. Input/Output condition : STATIC		OK	P																																																																																													

7	THERMAL SHOCK TEST	1. Thermal shock Temperature : -30°C ~ +50°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 10 CYCLE 5. Input/Output condition : 230VAC/Full Load AC ON/OFF TEST turn on 58sec ; turn off 2sec	OK	P
8	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10~500Hz (3) Sweep Time : 10min/sweep cycle (4) Acceleration : 5G (5) Test Time : 60min in each axis (X.Y.Z) (6) Ta : 25°C	TEST : OK	P
9	CAPACITOR LIFE CYCLE	HRP-450-24:SUPPOSE C105 IS THE MOST CRITICAL COMPONENT (1) I/P : 230VAC O/P : FULL LOAD Ta= 25 °C LIFE TIME (2) I/P : 230VAC O/P : FULL LOAD Ta= 50 °C LIFE TIME (3) I/P : 230VAC O/P : 75% LOAD Ta= 50 °C LIFE TIME	(1) 1849473HRS (2) 434362.5HRS (3) 502524HRS	P
10	MTBF	MIL-HDBK-217F NOTICES2 PARTS COUNT TOTAL FAILURE RATE : 139.9K HRS		P

TEST RESULT	TESTER	APPROVAL
PASS	SANFORD SU	VINCENT TSENG

2009/08/04 A50-F023